

ROSCOMMON COUNTY REMONUMENTATION

9078 8 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 21 10 51 AM '93

or corners in **COMMISSION**

<u>ROSCOMMON</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>22N</u> R <u>4W</u>	<u>G-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

*Robert L. Lapham*  
REGISTERED PROFESSIONAL SURVEYOR

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 11/30/93**

**TO BE FILED IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number**

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**TIMOTHY L. LAPHAM** in a field survey on November, 19 93,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- 3: 1852, A.CURTIS, POST, HEMLOCK 36" N32E 32L, B. OAK 15" S54W 30L;  
UNKNOWN, UNKNOWN, LCRC 2-255, CNR MAT, NO WIT;  
11/19/1970, L.CAVANAGH, PAVEMENT BOX;  
11/24/1973, SPICER, LCRC 1-93, CNR MAT, 4 WITS;  
10/4/1977, L.CAVANAGH, SURVEY 338-564, CNR MAT, 4 WITS;

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 3: FOUND 1/2" X 1/2" X 14" SQUARE SPIKE IN MON BOX. CONCRETE SLAB IN HOLE AT 2'+/- IN  
CENTERLINE RDS N-S-E-W  
C/L C.P. POLE S75E 182.32'  
C/L TOP MH S50W 45.18'  
C/L TOP R/W MARKER N75W 180.83'  
ACCEPTED FOUND CORNER AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER.  
THIS CORNER ESTABLISHED IN ROSCOMMON COUNTY REMONUMENTATION PROGRAM.  
SEE DOSSIER FOR DETAILED REPORT.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3: SET 2"X21" CAST IRON MONUMENT WITH BRASS ROSCOMMON COUNTY PLATE IN MONUMENT BOX  
AZ 224° 45.86' CENTERLINE TOP OF MANHOLE COVER  
AZ 240° 71.95' SPIKE AND TAG SE FACE UTILITY POLE  
AZ 322° 91.27' SE CORNER BRICK BASE FOR SIGN  
AZ 108° 181.45' CENTERLINE OF TOP OF RIGHT OF WAY MARKER



Signed by *Timothy L. Lapham* Date 12/20/93

Surveyor's Michigan License No. 27595

Date 11/30/93 Peer Group Approved  
LIBER 3 PAGE 42