

11550

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey
T22N R4W G-6
T R
T R
T R

FILE IN LIBER 3 OF LAND CORNER
STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED
22 DEC 98 12:24 P.M.
ROBERT W. SMITH
REGISTER OF DEEDS

I, Larry L. Cavanagh, in a field survey December, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration

ARTEMAS CURTIS 1852
SET QUARTER POST
ASPEN 10 N80W 20
ASPEN 11 S50E 20
DANEIL E. SCHRIPEMA RLS 24617, 1994
LIBER 690, PAGE 324
REC. 311, PAGE 189
LARRY L. CAVANAGH RLS 17614, 1972
LCRC
SET 1/2" X 18" BAR MID-WAY AND
ON LINE BETWEEN NE & SE
SECTION CORNERS
ROBERT L. HIGGINS RLS 21570, 1975
LIBER 311, PAGE 189
SET P.K. NAIL
6' MAPLE IN CLUMP S50°W 84.6'
12' SPRUCE N45°W 86.1'

Grid table with columns A-M and rows 2-12. A dot is marked at the intersection of column F and row 6.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO ORIGINAL OR SUBSEQUENT EVIDENCE OF THE CORNER WAS FOUND. CORNER WAS RE-ESTABLISHED MID-WAY AND ON LINE BETWEEN G-5 (N0°05'02"E 2636.26') AND G-7 (S0°05'02"W 2636.26')
A REESTABLISHMENT OF THE POSITION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614 1998 5± WEST OF HWY CENTERLINE
WIT: NAIL & TAG IN 8" MAPLE (IN CLUMP) S65°W 83.45'
NAIL & TAG IN 7" BALSAM N69°W 77.80'
NAIL & TAG IN 4" POPLAR S46°E 62.98'
CARSONITE POST S89°E 35.02'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE DEC 4, 1998

Marvin E. Myers, P.S.
County Surveyor

SURVEY &
REMONUMENTATION

MAR 01 1999

SECTION

Signed by [Signature]
Surveyor's Michigan License NO. 17614

Date 12/22/98



LIBER 3 PAGE 553