

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**

9274

DATE Dec 13, 1994

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

Roscommon

**SURVEY &
REMONUMENTATION**

Located In:

Corner Code #

21 DEC 94 9:52 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

1. Public Land Survey APR 24 1995 T 22N, R 4W H - 2
T _____ R _____
T _____ R _____
COMMISSION T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on Dec 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4					●		2			
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- G. Henning 5-18-1964
Mon- $\frac{1}{2}$ " bar
Cavanagh Oct. 1989 Act 74
L.1, pg.270
Mon-Fd. $\frac{1}{2}$ " Bar
 - Larry Cavanagh 7-29-89
Mon- $\frac{1}{2}$ " Bar
WIT: $\frac{1}{2}$ " Bar S89°31'25"E 280.9'
Spike in 4" Ash S49°E 96.52'
Spike in 4" Cherry S07°E 66.72'
Spike in Apple N33°W 139.02'
 - Cavanagh Apr. 1990
Mon- $\frac{1}{2}$ " Bar
WIT: Spike in 4" Cherry S07°E 66.72'
Spike in 4" Ash S49°E 96.52'
Spike in Apple N33°W 139.02'
 $\frac{1}{2}$ " Bar S89°31'25"E 280.9'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Monument - Found $\frac{1}{2}$ " Bar as established said location is based on a reasonable interpretation of the protraction delineated on the GLO map and being of long standing is accepted as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Monument-Set std. Roscommon County Mon. stamped "T22N, R4W, H-2 31600"
 - Wit-Found nail W. side 4" Cherry S02°E 66.65
 - Found nail NE side 4" Ash S46°E 96.44
 - SW cor. Conc. Curb N75°E 55.44
 - SE Cor. Conc. Block Bldg. (Carter's) N45°30'W 89.74
 - Set Carsonite Post 3.35
 - N83°49'16"W 2523.63 to G-2
 - S83°49'33"E 2424.10 to I-2
 - S06°06'48"W 2641.10 to H-3



Signed by Marvin E. Myers

Date Dec 20, 1994

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 211