

**SURVEY &  
REMONUMENTATION**

MAY 28 1997

**COMMISSION**

9565

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

23 DEC 96 10:06 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in ROSCOMMON Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T	<u>22N</u>	R	<u>4W</u>	<u>H-5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, Larry L. Cavanagh, in a field survey on November, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

POST SET BY ARDEMAS CURTIS 1852  
WIT: SPRUCE 10" N70°W 20 LKS  
CEDAR 12" S75°E 23 LKS

L. CAVANAGH JUNE 1994  
NO CORNER MATERIAL LISTED  
WIT: 10" POPLAR N64°W 66.39'  
6" OAK S31°W 63.08'  
6" MAPLE S18°E 43.84'  
3" MAPLE N64°E 61.29'

L. CAVANAGH 1977 LIBER 344, PAGE 33  
NO CORNER MATERIAL LISTED  
WIT: 5" MAPLE S50°W 62.9'  
5" MAPLE S20°E 43.72'  
8" MAPLE NORTH 76.0'

L. CAVANAGH NOVEMBER 1994  
NO CORNER MATERIAL LISTED  
WIT: SAME AS 1977 SURVEY (I 344, P33)

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE NOV 8<sup>TH</sup> 1996**

*Marvin E. Myers*  
**Marvin E. Myers, P.S.  
County Surveyor**

NOTE: ALL THE ABOVE ARE REFERENCED TO THE HENNING LOCATION (NOT ACCEPTED)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 1996 17614 AT SINGLE PROPORTIONATE DISTANCE BETWEEN G-5 AND I-5.  
SEE MAP AND REPORT IN DOSSIER

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 1996-17614  
WIT: 11" POPLAR N65°W 46.87'  
10" MAPLE S32°W 80.81'  
8" MAPLE S17°E 71.06'  
17" CEDAR N78°E 103.96'  
4" POPLAR N71°W 27.70'  
10" BAR ON CENTERLINE S10°E 27.61'  
CARSONITE POST N3°W 13.71'

A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.



Signed by *Larry L. Cavanagh* Date Dec 10, 1996  
Surveyor's Michigan License No. 17614

1. --- 2. Date 201