

**SURVEY &
REMONUMENTATION**

APR 24 1995

**ROSCOMMON COUNTY
PEER GROUP APPROVAL COMMISSION**

DATE December 6, 1994

**ROSCOMMON COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

| Roscommon (County) | Located In: | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T 22N R 4W | I - 7 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

16 DEC 94 2:37 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Marvin E. Myers, in a field survey on November 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered; found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Artemas Curtis 1852
Mon-Post
WIT: 16" Hemlock N15°E 47 lks.
28" Hemlock S25°W 31 lks.

Cavanagh 8-6-75
Mon-Fd. 1/2" Iron
WIT: 6" Cherry N64°W 83.00'
5" Aspen S74°W 64.20'

Cavanagh Oct. 1982 L.359, pg.96
Mon-Pav't Box
WIT: 6" Cherry N64°W 83.00'
5" Aspen S74°W 64.20'

Robert T. Ostling Aug. 1948
Mon-1/2"x15" Iron Rod in G. Roads
WIT: B.T. 6" Cherry N64°W 83.00'
B.T. 5" Aspen S74°W 64.20'

LCRC L.2, pg.265
Mon-1/2"x15" Iron Rod in G. Roads
WIT: B.T. 6" Cherry N64°W 83.00'
B.T. 5" Aspen S74°W 64.20'

Cavanagh Mar. 1988 L.566, pg.331
Mon-
WIT: 6" Cherry N64°W 83.00'
5" Aspen S74°W 64.20'

Gene Ostling May 1973 L.274, pg. 173
Mon-1/2" Iron Rod
WIT: 6" Cherry N64°W 83.00'
5" Aspen S74°W 64.20'

Cavanagh Oct. 1976
Mon-None
WIT: B.T. 6" Cherry N64°W 83.00'
B.T. 5" Aspen S74°W 64.20'


Cavanagh Dec. 1991
Mon-Iron in pav't box
WIT: 6" Cherry N64°W 83.00'
5" Aspen S74°W 64.20'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - Found 5/8" x 13" Bar in pavement box at centerline Nestle Road and 1.0' East of centerline Loxley Road Accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument - Set Std. Roscommon County Mon. Stamped "T22N R4W I-7 31600" in mon. box
WIT: Set nail NE cor. fence post S50°E 57.80'
Set nail SE side utility pole N55°E 59.20'
Set nail NE side 8" Poplar N44°W 42.25'
Set nail SE side S. gate post S29°W 81.60'



Signed by Marvin E. Myers

Date DEC 15, 1994

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983