

SURVEY &  
REMONUMENTATION

11507

MAR 01 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22NR 4W</u>	<u>I-10</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property In Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

SECTION

FILE IN LIBER 3 OF LAND CORNERS  
STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

22 DEC 98 9:07 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, In a field survey on Dec 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO - July 1852 John Brink, D.S. Mon - Post Wit: 8" Cedar N34°E 16 Lks 8" Cedar S45°W 24 Lks.	L1, P83-84 L. Cavanagh, P.S. 17614 April 1973 Mon - Found 1/2" pipe Wit: 3" Balsam S65°E 35.85 7" Balsam N7°E 62.95
	L2, P. 277 LCRC Mon - 1/2" Pipe Wit: 3" Balsam S65°E 35.85 7" Balsam N7°E 62.95

L 316, P. 609 May 1976  
L. L. Cavanagh, P.S. #17614  
Mon - 1/2" Pipe  
Wit: 3" Balsam S65°E 35.85  
7" Balsam N7°E 62.95

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2"x30" pipe in old brush line N-S distances L. Cavanagh, P.S. 17614 1973 Section retracement survey. Accepted 1/2" Pipe as the best available evidence of the position of the Original corner. Replaced pipe with standard Roscommon County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Mon - Standard Roscommon County Monument.  
Wit: Set Carsonite Post East 2.0  
Set PK nail & tag 12" Maple S15°E 35.96  
Set pk nail & tag 4" Balsam S44°W 36.97  
Set pk nail & tag 4" Balsam N39°W 20.14  
Set pk nail & tag 6" Twin Maple N34°E 27.86



ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE DEC 9, 1998

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

Signed by *Marvin E. Myers* Date December 17, 1998  
Surveyor's Michigan License No. 31600

LIBER 3 PAGE 543