

11508

SURVEY & REMONUMENTATION

MAR 01 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 22NR 4W

I-11

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SECTION

FILE IN LIBRARY OF MICHIGAN CORNERS  
ROSCOMMON COUNTY  
RECORDED

22 DEC 98 9:07 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on Dec 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO - July 1852 John Brink, D.S.  
Mon - Post

Wit: 8" Spruce N45°E 34 Lks  
15" Hemlock S60°W 24 Lks.

Sept 1948 G.D. Henning, P.S. #2240  
Mon - Corner of Record

L2, P. 285-286 LCRC  
Mon - 1 1/4" Pipe  
Wit: 7" Balsam S40°W 7.7  
5" Balsam S70°E 16.9

L. 263, P. 420 July 1972  
L. L. Cavanagh, P.S. #17614

Mon - Found 1 1/4" Pipe  
Wit: 7" Balsam S40°W 7.7  
5" Balsam S70°E 16.9

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1 1/4"x36" pipe with 1.2 feet of pipe above ground. Distances match L. Cavanagh, P.S. #17614 1973 Section retracement survey. Accepted 1 1/4" pipe as the best available evidence of the position of the Original corner. Replaced pipe with Standard Roscommon County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Mon - Standard Roscommon County Monument.

Wit: Set PK nail & tag 8" Oak N55°W 46.75  
Set PK nail & tag 12" Oak S84°W 31.50  
Set PK nail & tag 6" Balsam S87°E 51.52  
Set PK nail & tag 12" Oak N39°E 63.97  
Set Carsonite Post West 1.0



ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Dec 4, 1998

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date December 17, 1998

*LIBER 3 PAGE 544*