

**SURVEY &
REMONUMENTATION**

APR 24 1995

ROSCOMMON COUNTY COMMISSION

PEER GROUP APPROVAL

DATE Dec 13, 1994

ROSCOMMON COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

9209

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> , R <u>4W</u>	<u>J-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

16 DEC 94 2:39 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on Dec 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G. Henning/R. Ostling 7-25-45
Mon- Found 1/2" iron bar in fence intersection
G. Henning 2-11-47
WESTMORELAND SUB L.3, P18
Mon- Conc Mon,
Wit- None given
LCRC L.2, P262
Mon- 1/2" bar
Wit- None given

L. Cavanagh Sep 1990
Mon- Unknown
Wit- not given

L. Cavanagh June 1994
Mon- Unknown
Wit- None given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set Standard Roscommon County monument mark cap " 31600".
Wit- Found concrete monument N86°W 49.82
Set nail & tag E. side 28" Willow South 75.53
Set nail & tag NW side Utility Pole N45°E 5.19
Set nail & tag W. side 10" Tr. Elm N04°W 103.76
NW corner Concrete Block foundation S70°E 98.43
S03°58'40"W 2631.55 to J-5
N83°00'02"W 2644.59 to I-4

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Marvin E. Myers Surveyor's Michigan License No. 31600

Date Dec 15, 1994

