

SURVEY & REMONUMENTATION

MAR 01 1999

11509

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED  
FILE IN LIBER 3 OF LAND CORNERS  
22 DEC 98 9:07 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Roscommon  
(County)

Located in:

Corner Code #

1. Public Land Survey

T 22NR 4W

J-11

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on November 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				
5													
6	18		17		16		15		14				
7													
8	19		20		21		22		23				
9													
10	30		29		28		27		26				
11													
12	31		32		33		34		35				
13													

A. Description of original monument and accessories and/or subsequent restoration:  
GLO - July 1852 John Brink, D.S.  
Mon - Post  
Wit: 16" Y. Pine N60°E 4 Lks  
12" Y. Pine S25°W 19 Lks.

L. 382, P. 30 (Same data as below)  
LCRC L. 1, P 192 April 26, 1979  
Larry L. Cavanagh, P.S. #17614  
Mon - 1/2" Bar  
Wit: Fence Corner South 40.8  
4" Poplar N70°E 50.24  
3" Cherry N70°W 53.42  
1/2" Bar N0°20'W 33.0

L. 263 P. 417 1972  
L. L. Cavanagh PS # 17614  
Mon - found 1/2" bar  
Wit: None given

L. 370, P. 370  
April 1978 L. L. Cavanagh, P.S. #17614  
Mon - Not Given  
Wit: Fence Corner Post South 40.8  
4" Poplar N70°E 50.24  
3" Cherry N70°W 53.42


LCRC L. 2, P. 286  
Mon - 1/2" bar  
Wit: Fence Corner Post South 40.8  
4" Poplar N70°E 50.24  
3" Cherry N70°W 53.42

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2" bar in fence N-S & W in line with centerline of Road East; found 3" (now 8") Cherry N70°W 53.42 Accepted 1/2" bar as the best available evidence of the position of the Original Corner. Replaced bar with Standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Mon - Standard Roscommon County Monument.  
Wit: Set PK nail & tag 8" Twin Black Cherry N75°W 53.60  
Set PK nail & tag 8" Poplar N21°W 17.32  
Set PK nail & tag 8" Twin Black Cherry S72°E 6.80  
Set PK nail & tag Fence Post S11°E 33.89  
Set Carsonite Post West 2.0

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Dec 4, 1998

Marvin E. Myers  
Marvin E. Myers, P.S.  
County Surveyor



Signed by \_\_\_\_\_

Surveyor's Michigan License No. \_\_\_\_\_

Date December 17, 1998