

SURVEY & REMONUMENTATION

APR 24 1995

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**

DATE Dec 6, 1994

COMMISSION

ROSCOMMON COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 4W	K -6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

16 DEC 94 2:38 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on November 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


GLO-Artemas Curtis Sept. 1852 Mon-Post WIT: 14" Y.Pine N15°W 42 lks. 15" Y.Pine S55°E 15 lks.	MSHD Sept. 1958 Mon-3/4" iron pipe WIT: 8" Oak N44°E 71.08' 9" Oak S75°E 47.06' 10" Oak S60°E 62.71'	L.1, pg.119 LCRC Mon- WIT: 6" B.Oak S45°W 90.50' 10" B.Oak N61½°W 81.00' 14" B.Oak N44½°E 106.80'
G.Henning 7-7-93 Mon-None Given WIT: None Given	L.2, pg.264 Mon-iron in Mon. Box WIT: 8" Oak N44°E 71.08' 9" Oak S75°E 47.06' 10" Oak S60°E 62.71'	Cavanagh 8-15-1979 L.1, pg.212 LCRC Mon-Conc. Mon. WIT: Pipe West 33' 6" B.Oak S45°W 90.50' 10" B.Oak N61½°W 81.00' 14" B.Oak N44½°E 106.80'
G.Henning Feb. 1947 Recorded plat of HILLSIDE L.3, pg.16 Mon-1"x24" Pipe WIT: B.T. 6" B.Oak S45°W 90.50' B.T. 10" B.Oak N61½°W 81.00' B.T. 14" B.Oak N44½°E 106.80'	Ostling Surveys Aug. 1963 Mon- WIT: 6" B.Oak S45°W 90.50' 10" B.Oak N61½°W 81.00' 14" B.Oak N44½°E 106.80'	Cavanagh June 1980 Mon-4" Conc. Mon. in road WIT: Pipe West 33' 6" B.Oak S45°W 90.50' 10" B.Oak N61½°W 81.00' 14" B.Oak N44½°E 106.80'
G.Henning 5-22-47 Mon-4" Conc. Mon. in road WIT: Pipe West 33' 6" B.Oak S45°W 90.50' 10" B.Oak N61½°W 81.00' 14" B.Oak N44½°E 106.08'	Cavanagh July 1978 L.355, pg.515 Mon- WIT: 6" B.Oak S45°W 90.50' 10" B.Oak N61½°W 81.00' 14" B.Oak N44½°W 106.80'	L.Cavanagh 4-17-1984 L.1, pg. 271 LCRC Mon-Iron in pav't box WIT: 6" B.Oak S45°W 90.50' 10" B.Oak N61½°W 81.00' 14" B.Oak N44½°E 106.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - Found 1½" x 21" O.D. Pipe in Mon. Box 1.4' East of centerline Tower Hill Road and centerline Crestview Road
WIT: Fd. nail SE side U.P. S31°W 55.15'
Fd. blaze NW face 11" W.Oak S48°E 59.50' Accepted as the best available evidence of the position of the original corner.
Fd. wit. tag & nail "JLS 26466" SW side
12" Tw.W.Oak N42°E 54.44"
Fd. blaze SW face 20" B.Oak N56°E 106.50'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument- Set Std. Roscommon County Mon. stamped "T22N R4W K-6 31600" in Mon. Box
WIT: Fd. nail SE side U.P. S31°W 55.15'
Fd. wit. tag & nail "JLS 26466" SW side
12" Tw.W.Oak N42°E 54.44"
Set wit. tag & nail NE side 11" W.Oak S48°E 60.24"
Set wit. tag & nail SW side 22" R.Oak N55°W 81.22'



Signed by Marvin E. Myers

Date Dec 15, 1994

Surveyor's Michigan License No. 31600