

MAR 01 1999

11512

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

STATE OF MICHIGAN
FILE IN LIBER ROSCOMMON COUNTY CORNERS
RECORDED

Roscommon
(County)

Located In:

Corner Code #

22 DEC 98 9:08 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

- | | | |
|------------------------------------|------------------|-------------|
| 1. Public Land Survey | T <u>22NR 4W</u> | <u>K-10</u> |
| | T <u> R</u> | <u> </u> |
| | T <u> R</u> | <u> </u> |
| | T <u> R</u> | <u> </u> |
| 2. Property Controlling in Section | S <u> T</u> | <u> </u> |
| | S <u> T</u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> T</u> | <u> </u> |
| | S <u> T</u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on November 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - July 1852 John Brink, D.S
Mon - Post
Wit: 12" S. Pine N68°W 20 Lks
5" S. Pine S37°E 27 Lks.

L. 400, P. 292 Mar 1979
George D. Henning, P.S. #2240
Mon - Found 1/2" bar
Wit: 8" W. Oak S52°30'E 58.8
5" Oak N50°30'E 37.7

L. 481, P. 374 Dec 6, 1985, P.S. #17614
Mon - Not given
Wit: 8" W. Oak S52°30'E 58.8
5" Oak N50°30'E 37.7

LCRC L. 1, P. 83-84 April 1973
Mon - Found 3/8" Bar
Wit: 6" Oak S75°W 22.67
6" W. Oak S40°E 58.6
8" Maple N75°E 57.3

LCRC L. 1, P. 192 April 1979
Larry L. Cavanagh, P.S. #17614
Mon - 3/8" Bar
Wit: 6" Oak S75°W 22.67
6" W. Oak S40°E 58.6
8" Maple N75°E 57.3
5" Oak N50 1/2°E 57.75

LCRC L. 1, P. 312 Feb 1991, P.S. 27595
Mon - Found Sq. bolt in Mon. Box
Wit: SE cor. Stonewall N50°W 34.2
Face 10" Poplar S50°W 47.8
Face Power Pole East 31.2
Face Power Pole N40°E 56.1

L. 337, P. 35 Nov 1976
Frank J. Arleth, P.S. # 21266
Mon - Found 1/2" Bar
Wit: 8" W. Oak S52°30'E 58.8
5" Oak N50°30'E 37.7

L. 384, P. 380 Oct 1979 P.S. 17614
Mon - Not given
Wit: 8" W. Oak S52°30'E 58.8
5" Oak N50°30'E 37.7

LCRC L. 2, P. 276
Mon - 1/2" x 24" Iron Bar
Wit: 8" W. Oak S52°30'E 58.8
5" Oak N50°30'E 57.7

See Dossier for additional data

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" x 27" sq. top bolt over the top of a 1/2"x30" bar with tip rusted to a point; found 6" W. Oak S40°E 58.6; found 8" Maple N75°E 57.3; found 5" Oak N50 1/2°E 57.7; found 8" W. Oak S52 1/2°E 58.8; found SE Cor Stone Wall N50°W 34.2; found Power Pole East 31.2; found P. Pole N40°E 56.1. Accepted bolt as the best available evidence of the Position of the Original Corner. Replaced bolt with Standard Roscommon County Monument in pav't monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon - Standard Roscommon County Monument in pavement monument box.


Wit: N. edge of Carsonite Post N87°W 27.41
Face of Power Pole N40°E 56.1
Face of Power Pole East 31.2
SE corner of Stone Wall N50°W 34.2

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 9, 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by _____
Surveyor's Michigan License No. 31600

Date December 17, 1998



LIBER 3 PAGE 548