

JAN 24 1995

TO BE FILED IN LIBER 3 OF LAND CORNERS

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Table with columns: For corners in Roscommon (County), Located In: (Town, Range, Section), Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

STATE OF MICHIGAN ROSCOMMON COUNTY RECORDED

25 OCT 95 1:40 P.M.

Register of Deeds Stamp & File Number

REGISTER OF DEEDS

Grid for Register of Deeds with columns A-M and rows 1-13. A dot is present in cell J9.

4. Lot No. , Recorded Plat
5. Private Claims

I, Larry L. Cavanagh, in a field survey on September, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set Post 1852 Artemas Curtis Y. Pine 18" N48°W 13 Y. Pine 16" S36°E 22
Liber 2, Page 276 LCRC (1970's) 1/2" bar in corner 3" Maple S15°E 39.3 7" Poplar N25°E 42.5
Certificate of survey 1994 Cavanagh Found 1/2" bar in corner S23°E 36.61' 8" Oak S1°E 31.35' P. Pole N16°W 42.31' 5" Poplar N36°E 55.40' 8" W. Pine
1944 & 1957 Henning Survey shows no corner reference corner shown as mid-way and on line
Liber 1, Page 77-78 LCRC 1973 Cavanagh same as above
Henning recorded survey 1979 Liber 400, Page 293 Found 1/2" bar in corner Same witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" steel bar in corner N16°W 42.39' Nail in 5" Poplar N36°E 55.46' Nail in 8" W. Pine S23°E 36.56' Nail in 8" W. Oak S 1°E 31.29' Nail in Power Pole Found on line with section corners 0.08' East of mid-way, recent measurement.


ROSCOMMON COUNTY PEER GROUP APPROVAL DATE 9-8-1995

Marvin E. Myers, P.S. County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon County standard monument and pavement box stamped 17614-1995 N16°W 42.39' Nail in 5" Poplar N36°E 55.46' Nail in 8" W. Pine S23°E 36.56' Nail in 8" W. Oak S 1°E 31.29' Nail in Power Pole North 28.72 carsonite post

Is accepted as the best available evidence of the position of the original corner.



Signed by [Signature] Surveyor's Michigan License No. 17614

Date Oct 16, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983