

9163

SURVEY & REMONUMENTATION

ROSCOMMON COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

MAY 28 1997

COMMISSION

For corners in

Form with fields for ROSCOMMON (County), Located In, Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

STATE OF MICHIGAN ROSCOMMON COUNTY RECORDED

6 DEC 96 4:25 P.M.

ROBERT W. SMITH REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS Register of Deeds Stamp & File Number

I, TIMOTHY L. LAPHAM, in a field survey on July, 9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13 for recording corner locations.

A. Description of original monument and accessories and/or subsequent restoration:

M -11 GLO, BRINK 1836, SET POST, 12" WHITE PINE S31W 30 LNKS, 12" YELLOW PINE N24W 26 LNKS; LCRC, UNKNOWN (REC 2-276), 1/2" BAR, 3 WITS; PLAT OF HIGHLAND ACRES, OSTLING (REC 6-75, 12/30/1970), NO MONUMENT MATERIAL OR WITS; SURVEY, CAVANAGH (REC 437-474-6, 2/09/1983), NO MONUMENT MATERIAL OR WITS;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M -11 NO EVIDENCE OF GLO FOUND. FOUND 1/2" BAR IN ACCORD WITH RECORDED LCRC. DISTANCE SOUTH MATCHES PLAT OF HIGHLAND ACRES. ACCEPTED FOUND MONUMENT AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER. SEE DOSSIER FOR ADDITIONAL INFORMATION.

ROSCOMMON COUNTY PEER GROUP APPROVAL DATE Dec 16th 1996

Signature of Marvin E. Myers, P.S., County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M -11 SET 2" X 21" CAST IRON MONUMENT WITH BRASS ROSCOMMON COUNTY PLATE IN MONUMENT BOX. N46E 108.41' 12" OAK, NAIL IN SOUTH SIDE OF TREE S24E 61.51' 10" OAK, NAIL IN EAST SIDE OF TREE S46W 41.84' GUIDE POLE, NAIL IN WEST SIDE OF POLE N42W 41.04' UTILITY POLE, NAIL IN EAST SIDE OF POLE

Signed by [Signature] Surveyor's Michigan License No. 27595

Date 10/01/1996

