

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
ROSCOMMON
 (County)

		Located In		Corner Code #
1. Public Land Survey	T	<u>22N</u>	R <u>4W</u>	<u>A-10</u>
	T	<u>22N</u>	R <u>4W</u>	<u>A-11</u>
2. Property Controlling in Section	S	_____	R _____	_____
	S	_____	R _____	_____
3. Miscellaneous Property in Section	S	_____	R _____	_____
	S	_____	R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on NOV. 17, 1998 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-10 GLO - JULY 1852 - ARTEMUS CURTIS, D.S.
 SET QUARTER SECTION POST.
 WIT: WHITE PINE 12" S02° W 26 LINKS
 MAPLE 7" N71° W 55 LINKS

A-11 GLO - JULY 1852 - ARTEMUS CURTIS, D.S.
 WHITE PINE 12" DIAMETER FOR CORNER.
 WIT: WHITE PINE 18" N77° E 36 LINKS
 WHITE PINE 16" S45° E 27 LINKS

JACK ERICKSON, RLS # 16929 - 1969 SET CONCRETE MONUMENT BY PROPORTIONATE MEASUREMENT.

MARCUS SCHAFF, RLS # 3104 - c. 1940 SET A 1 1/4" PIPE WITH CONCRETE BASE.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

A-10 FOUND AND ACCEPTED A CONCRETE MONUMENT AS SET BY JACK ERICKSON, RLS # 16929.

A-11 FOUND AND ACCEPTED A 1 1/4" PIPE WITH CONCRETE BASE AS SET BY MARCUS SCHAFF, RLS # 3104.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 CONCRETE MONUMENT
 SET CARSONITE POST NORTH 1'.
 WIT: * 7" WHITE PINE N07° W 22.93'
 * 8" WHITE OAK N58° W 33.23'
 * 11" RED OAK S34° W 29.03'
 6" RED MAPLE S59° E 48.40'

* OLD WITNESS BY OTHERS

A-11 SET 5/8" REROD WITH CAP INSIDE PIPE & CARSONITE POST NORTH 1'.
 WIT: * 14" OAK N55° W 12.45'
 * 20" OAK N74° E 44.61'
 10" OAK S21° E 27.44'
 10" OAK S30° W 46.47'
 1/2" REROD NORTH 0.9'

* OLD WITNESS BY OTHERS

Signed by:

Carl T Kiiskila

Date:

6-22-99

Surveyor's Michigan License No.:

33981

