

9165

MAY 28 1997

ROSCOMMON COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

ROSCOMMON
(County)

Located in: Corner Code #

- | | | |
|------------------------------------|-------------------|----------------|
| 1. Public Land Survey | T 23NR 3W | M - 6 |
| | <u>T 23NR 2W</u> | <u>A - 6</u> ✓ |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

6 DEC 96 4:25 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, TIMOTHY L. LAPHAM, in a field survey on July, 15, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M - 6 BURT 1838, SET POST 6" Y.PINE S26W 20 LINKS, 6" Y.PINE N34W 26 LINKS;
LCRC, JOHNSON, 1/28/92 (REC 1/28/92, L1, P305), FOUND 1/2" BAR, 8" RED OAK S38E 60.6',
6" RED OAK N61E 62.3', 5" RED OAK N62W 49.3', 12" RED PINE S86W 64.9';
LCRC, ROSER, NO DATE (REC 6/6/94, L1, P326), RE-RECORDED JOHNSON'S LCRC;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 6 NO EVIDENCE OF GLO FOUND, FOUND 1/2" IRON IN ACCORD WITH RECORDED LCRC. ACCEPTED FOUND CORNER AS BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. SEE DOSSIER FOR ADDITIONAL INFORMATION.


ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE APR 16 TH 1996

Marvin E. Myers
Marvin E. Myers, P.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 6 SET 2"X24" CAST IRON MONUMENT WITH BRASS ROSCOMMON PLATE FROM WHICH:
S38E 60.6' 8" RED OAK N62W 49.3' 5" RED PINE
N61E 62.3' 6" RED OAK S86W 64.9' 12" RED PINE

Nail and tags in all trees



Signed by *Timothy L. Lapham*
Surveyor's Michigan License No. 27595

Date 10/1/1996