

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
 Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N R2W D-1
 T24N R2W D-13
 T R _____
 T R _____

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

11 JUL 97 4:10 P.M.

ROBERT W. SMITH
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey June 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

SET POST BY WILLIAM BURT, 1852
 WIT: W. BIRCH 5 N5°E 3
 CEDAR 5 N85°W 11

KENNETH J. OSTLING RLS 10068, 1983
 SET DNR MONUMENT
 WIT: 10" HEMLOCK, N34°W 50.7'
 16" CEDAR N69°W 26.5'
 6" CEDAR S37°W 21.5'
 DNR MON S0°04'44"W 1568.91'
 SET 4" CEDAR POST BY CORNER

SCHAAF RECORD INDICATES
 FOUND AND REPLACED

(IN OLD 14"x17" SURVEY BOOK, REG
 OF DEEDS)
 G.F. DALAMATER 1932
 SET 1/2" X 30" BAR @ COR PLACED
 MID-WAY ON LINE
 HEM 7" N34°W 50.7'
 CEDAR 6" N69°W 25.5'

CARL KIISKILA RLS, 1997
 LIBER 744, PAGE 14 (RECORDED SURVEY)
 FD DNR MON. SET BY K.J. OSTLING IN 1983
 10" HEMLOCK N34°W 50.7'
 16" CEDAR N69°W 26.5'
 6" CEDAR S37°W 21.5'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND DNR MONUMENT
 10" HEMLOCK N34°W 50.7'
 16" CEDAR N69°W 26.5'
 6" CEDAR S37°W 21.5'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR MONUMENT LEFT IN PLACE
 NAIL & TAG IN 10" HEMLOCK N34°W 50.7'
 NAIL & TAG IN 6" CEDAR S37°W 21.5'
 *NAIL & TAG IN 10" MAPLE S86°W 10.41'
 *NAIL & TAG IN 5" BALASM S86°E 53.09'
 CARSONITE POST NORTH 2.54'

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

* NEW WITNESSES

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
 DATE July 8, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
 County Surveyor



Signed by *Larry L. Cavanagh*
 Surveyor's Michigan License NO. 17614

Date July 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

LIBER 3 PAGE 413