

4554

SURVEY & REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields: For corners in Roscommon (County), Located In: T 23N R 2W, Corner Code # I-7, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Section, 4. Lot No., 5. Private Claims

SECTION STATE OF MICHIGAN ROSCOMMON COUNTY RECORDED 10 JUL 97 2:15 P.M. ROBERT W. SMITH REGISTER OF DEEDS FILE IN LIBER 3 OF LAND CORNERS Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column H and row 7.

I, Marvin E. Myers, in a field survey on 12 June, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - John Brink - 1852
Mon. - Post
WIT: 8" Hemlock N64°W 14 lks.
12" Hemlock S67°E 5 lks.

DNR - Schaaf - 1935±
Mon. -
Found or established, and replaced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" pipe (typical Schaaf monument); and accepted as the best available evidence of the position of the Original corner. Replaced monument with Std. 22" Roscommon County monument.

ROSCOMMON COUNTY PEER GROUP APPROVAL DATE July 8, 1997 Marvin E. Myers M.E.M. Marvyn E. Myers, P.S. County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Std. 22" Roscommon County Mon.
WIT: spike E. side 6" Poplar N36°W 12.21'
spike N. side 4" Poplar N86°E 13.32'
spike W. side 14" Maple in clump S28°E 72.93'
spike W. side 36" Red Oak with blaze S29°W 33.08'
Carsonite post North 1.05'



Signed by Marvin E. Myers Surveyor's Michigan License No. 31600

Date July 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

LIBER 3 PAGE 409