

4626

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N	R 2W	J-1
T24N	R2W	J-13
T	R	
T	R	

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

11 JUL 97 4:11 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

I, Larry L. Cavanagh, in a field survey June 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

SET POST BY WILLIAM BURT, 1852
WIT: TAMARACK 12 N70E 18
TAMARACK 10 N54W 29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO ORIGINAL EVIDENCE FOUND. THIS CORNER WAS RE-ESTABLISHED BY SINGLE PROPORTIONATE DISTANCE BETWEEN I-1 AND L-1.
J-1 TO I-1 S89°02'47"W 2644.43'
J-1 TO L-1 N89°02'47"E 5288.87'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 5' BLACK IRON PIPE & CAP 17614 (IN SWAMP)
NAIL & TAG IN 3" MAPLE S50°E 4.25'
NAIL & TAG IN 3" SPRUCE N14°W 32.67'
NAIL & TAG IN 18" W. PINE N1°E 29.84'
CARSONITE POST WEST 1.53'

A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE July 8, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date July 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 419