

APR 07 1998

4555

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Roscommon (County) Located In: Corner Code #
1. Public Land Survey T 23N R 2W J-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

10 JUL 97 2:15 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Marvin E. Myers, in a field survey on 12 June, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column J and row 7.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - John Brink - 1852
Mon. - Post
WIT: 7" Tamarack N31°W 11 lks.
6" Spruce S12°W 19 lks.
DNR - Schaaf 1935±
Mon. -
Found or established, and replaced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" pipe (typical Schaaf monument); and is accepted as the best available evidence of the position of the original corner. Replaced monument with Std. Roscommon County monument.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE July 8, 1997

Signature of Marvin E. Myers, P.S.
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Std. 22" Roscommon County Mon.
WIT: spike N. side 6" Cedar N19°W 6.66'
spike NW. side 6" Cedar S35°W 4.03'
spike N. side 8" Tamarack S51°E 10.10'
Found Delamater tag SW. side 10" Cedar N56°E 14.19'
set Carsonite Post West 0.89'



Signed by [Signature]
Surveyor's Michigan License No. 31600

Date July 9, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 410