

SURVEY & REMONUMENTATION

024

MAY 28 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>2W</u>	<u>K - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

17 JUN 96 3:40 P.M.

ROBERT W. SMITH
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on April 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-William Burt 1852 Mon-Post WIT: 8" Spruce N02°W 11 lks. 8" Cedar S76°E 15 lks.	G.D. Henning Feb. 9, 1946 Mon-Fd. old post & SE US B.T. Set Cedar Post in corner WIT: Mrk NBT on 7" Cedar S43°W 37.00' Mrk NBT on 6" Cedar N29½°E 42.60' Mrk NBT on 6" Cedar N11½°W 45.20'
---	---

ROSCOMMON COUNTY
PEER GROUP APPROVAL
 DATE April 8, 1996

Marvin E. Myers
Marvin E. Myers, P.S.
 County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found blaze 9" Cedar N05°W (recorded as N11½°W) 45.20
 Found blaze "NBT" 8" Cedar N35°E (recorded as N29½°E) 42.60'
 Found blaze 10" Cedar S50°W (recorded as S43°W) 37.00'
 Found very old and deep blaze (unknown survey, however much older than Henning 1946 survey) S15°W 4.30'
 Found remains of both GLO bearing trees
 Set standard county monument at intersection of witness as a perpetuation of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument - Set standard Roscommon County monument stamped "31600"
 WIT: Set nail & tag SE side 6" Cedar S65°W 21.79'
 Set nail & tag NE side 5" Cedar S23°E 15.71'
 Set nail & tag S. side 4" Cedar N61°W 12.16'
 Found blaze set pole barn nail in E. side at same distance as blaze S15°W 4.30'
 Set nail & tag E. side 6" Cedar N52°E 3.65'
 Set carsonite post N77°W 0.82'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by *Marvin E. Myers* Date April 11, 1996

Surveyor's Michigan License No. 31600