

**SURVEY &  
REMONUMENTATION**

MAY 28 1997

2390

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Roscommon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>2W</u>	<u>K - 8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

TO BE FILED IN LIBER 3 OF LAND  
CORNERS

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

18 APR 96 10:01 A.M.

Register of Deeds **INDEXED & FILED** Number  
REGISTER OF DEEDS

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Marvin E. Myers, in a field survey on February 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO - William Burt 1852  
Mon.-Set Post  
WIT: 12" Cedar N54°E 6 lks.  
10" Cedar N79°W 6 lks.  
G.D. Henning Feb. 9, 1946  
Mon.-Set 1"x24" Pipe & Post at midpoint  
WIT: Mkd. B.T. on 6" Cedar S23°W 20.20'  
Mkd. B.T. on 6" Cedar N24°W 37.40'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Monument - Found 1" x 24" pinch pipe replaced with 3/4" ID X 60"  
Verified position by measurements 1946 survey by George Henning distance 2637.4'(R&M) to K-9 accepted as a reestablishment of the position of the original government corner.

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE APRIL 8, 1996**

*Marvin E. Myers*  
**Marvin E. Myers, P.S.  
County Surveyor**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon.-Set 3/4" ID x 60" pipe & cap "MEM 31600"  
WIT: Set carsonite post along side monument  
Set nail & tag NE side 7" Maple N35°W 27.52'  
Set nail & tag N. side 5" Cedar N74°W 27.29'  
Set p.k. nail & tag SW side 6" W. Birch N37°W 138.75'  
Set p.k. nail & tag NW side 6" Cedar N51°E 110.07'



Signed by Marvin E. Myers

Date April 11, 1996

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 282