

**SURVEY &
REMONUMENTATION**

2397

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in <u>Roscommon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>2W</u>	<u>K - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

TO BE FILED IN LIBER 3 OF LAND CORN

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

18 APR 96 10:02 A.M.

Register of Deeds **Stamp # 31600** Number
REGISTER OF DEEDS

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Marvin E. Myers, in a field survey on February 19, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO - William Burt 1852
- Mon. - Set Post
- WIT: 10" Cedar N62°W 30 lks.
- 10" Cedar S86°E 12 lks.
- G.D. Henning Feb. 9, 1946
- Mon. - Fd. 1 1/2" pipe & both U.S. B.T.'s
- WIT: Fd. mkd. NBT 8" Cedar N43°E 29.90'
- Fd. mkd. NBT 7" Cedar N06 1/2°W 26.50'
- Fd. mkd. NBT 10" Cedar S76°W 40.60'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Monument - Found 1 1/2" ID x 62" pipe
- WIT: Found 9" Cedar stump marked "NBT" N32°E 29.90'
- Accepted as a perpetuation of original corner.

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE April 8, 1996**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon. - Set standard Roscommon County Monument stamped "31600" in exact location of pipe
- WIT: Set carsonite post S14°E 1.64'
- Set nail & tag E. side 3" Balsam N67°E 2.67'
- Set nail & tag E. side 4" Balsam S62°W 2.60'
- Set nail & tag N. side 9" Cedar N47°W 11.90'
- Set Fd. pipe N67°E 0.40'



Signed by *Marvin E. Myers* Date *April 11, 1996*
Surveyor's Michigan License No. 31600

LIBER 3 PAGE 289