

**SURVEY &
REMONUMENTATION**

2396

MAY 28 1997

COMMISSIONED CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Roscommon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>2W</u>	<u>L - 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

TO BE FILED IN LIBER 3 OF LAND CORNERS

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

18 APR 96 10:02 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on March 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-William Burt 1852	M. Schaaf 1935±
Mon-Set Post	Mon-Fd. but not replaced
WIT: 7" Tamarack N84°W 16 lks.	
7" Tamarack S60½°E 28 lks.	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1½" Schaaf pipe. Pipe broke off below surface. Set standard Roscommon County Monument over top. Accepted as best available evidence of the position of the original corner. L-5 to M-5 2553.18(M)

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**

DATE April 8, 1996

Marvin E. Myers

**Marvin E. Myers, P.S.
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Standard Roscommon County Monument
WIT: Set nail & tag SW side 4" Cedar AZ 330° 2.92'
Set nail & tag S. side 6" Tamarck AZ 72° 5.17'
Set nail & tag SW side 8" Tamarck AZ 152° 15.80'
Set nail & tag N. side 4" Triple Black Spruce AZ 285° 9.70'
Set carsonite post along side

Signed by *Marvin E. Myers*

Date April 11, 1996

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 288