

**SURVEY &  
REMONUMENTATION**

2395

MAY 28 1997

**LAND CORNER RECORDATION CERTIFICATE  
COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon  
(County)

Located in:

Corner Code #

- |   |   |            |   |           |       |
|---|---|------------|---|-----------|-------|
| 1. Public Land Survey                   | T | <u>23N</u> | R | <u>2W</u> | M - 7 |
|   | T | _____      | R | _____     | _____ |
|   | T | _____      | R | _____     | _____ |
|   | T | _____      | R | _____     | _____ |
| 2. Property Controlling<br>in Section   | S | _____      | T | _____     | R     |
|   | S | _____      | T | _____     | R     |
| 3. Miscellaneous<br>Property in Section | S | _____      | T | _____     | R     |
|   | S | _____      | T | _____     | R     |

TO BE FILED IN LIBER 3 OF LAND CORNER:

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

18 APR 96 10:02 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on February 13, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO-William Burt 1852 Mon-Set Post WIT: 12" Cedar S42°W 21 lks. 12" Cedar N45°W 13 lks.	G.D. Henning Feb. 9, 1946 Mon-1 1/2" Pipe & Post Chaining from East & West Confirm Position No witnesses near	M. Schaaf Mon-Fd. or established and replaced
--	---	--

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Monument - Found 1 1/2" pipe in concrete leaning Northwesterly (left in place) Set 3/4"x54" pipe & cap at base  
WIT: Iron fence posts East, South & West  
Accepted as best available evidence of the position of the original corner.

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE April 8, 1996**

*Marvin E. Myers*  
**Marvin E. Myers, P.S.  
County Surveyor**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Monument - Set 3/4" ID x54" pipe & cap "MEM 31600" at base of found pipe  
WIT: Iron fence post S80°E 1.00'±  
Set carsonite post South 2.60'  
Set nail & tag E. side 17" pine stump N32°E 39.88'  
Set 4' wood stake 3' into ground S40°E 7.75'  
Set 4' wood stake 3' into ground N80°W 7.50'  
Iron fence posts East & West & South

Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date April 11, 1996