

8596

SURVEY & REMONUMENTATION

ROSCOMMON COUNTY

PEER GROUP APPROVAL

DATE 10-20-94

MEM

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirements of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

22 NOV 94 11:07 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in

ROSCOMMON (County)	Located In:	Corner Code #
1. Public Land Survey	T 23N R 3W	F-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on October 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO- Artemas Curtis 1852
 Mon- Set Post
 Wit- 14" W. Pine S44°W 29 lks
 Houghton Lake West 1.98 Chains

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position is now in Houghton Lake. Position verified by measurement to accessories and corners of record and accepted as a careful and faithful establishment of the position of the corner. Set reference monument on South Section Line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Std. Roscommon County Monument marked " Ref. Mon. to F-11, T23N, R3W"
 WIT: N89°53'27"E 2581.33' to G-11 from ref. Mon.
 S89°53'27"W 60.07' to F-11 from ref. Mon.
 Set Nail & Tag W. face 15" Elm N38°E 4.64'
 Set Nail & Tag SW face 29" R.Oak S28°E 21.99'
 Set Nail & Tag W. face 13' R.Pine S04°E 41.99'
 NW corner footing boathouse N87°E 9.67'
 SW corner footing boathouse S30°E 16.00'
 Waters edge S89°W 19'±



Signed by Marvin E. Myers

Date October 20, 1994

Surveyor's Michigan License No. 31600

LIBER 3 PAGE 167