

Dec 28 10 28 AM '93

9244  
FEB 13 1984

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

*Robert H. Myers*  
REGISTER

Roscommon County	Located In:	Corner Code #
1. Public Land Survey	T 23N R 3W	G-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 12-7-93

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on Nov 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO - May 1852 Curtis  
Mon. - Post  
WIT: 10" W.Pine n45°E 47 lks.  
18" Y.Pine S40°W 32 lks.
- Misc. Records Reg. of Deeds  
L.2, pg. 363  
Mon. - 1/2" Iron Rod in Mon. Box  
WIT: C School Rd.
- K. Ostling Nov. 1978  
L. 357, pg. 228  
Mon. - None given
- L. Cavanagh Feb. 1977  
L. 331, pg. 449  
Mon. - Fd. 1/2" Bar in pav't box  
WIT: 30" Twin W.Oak N25°W 46.00'  
4" W.Oak S60°W 63.62
- R. Higgins Nov. 1975  
L. 312, pg. 327  
Mon. - Fd. 1/2" Bar pav't box
- L. Cavanagh Oct. 1990  
Mon. - Bar in pav't box  
WIT: Tag in 30" Tw. W.Oak N17°W 47.20'  
54" W.Oak S60°W 63.35'  
Spike in P.Pole S35°E 52.6
- R. Ostling Aug. 1957  
Mon. - 12" Spike over 1" pipe  
WIT: 10" R.Oak N48°E 35.85'  
14" Tw. W.Oak N17 1/2°W 46.35'
- May 1989 M. E. Myers  
Mon. - Fd. Sq. Head Bolt in Pav't Box  
WIT: Face Utility Pole S23°E 52.20'  
Seasonal Road Sign Post S12°W 43.40'  
Buried Cable Sign Post S42°W 37.00'  
Concrete Mon. S50°W 46.30'
- Nov. 1952 Work Map G. Henning  
Mon. - 1 1/2" Pipe 12" deep C roads 1/2" Bolt over pipe  
WIT: 7" B.Oak N48 1/2°W 35.80'  
18" Tw.Oak N17°W 46.30'  
8" B.Oak S16 1/2°E 68.60'

Sept. 1974 C. Ostling  
L.298, pg. 53W  
Mon. - Spike in pav't box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.  
Found Square Head Bolt over top of 1 1/2" x 24" Pipe in Pav't box in center of N-S & E-W Road intersection and accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon- Replaced bolt and pipe with Std. Roscommon County Monument.
- Wit- Found nail in Power Pole S35°E 52.6  
Found Blaze in 12" Spruce N67°E 137.7  
Found nail and tag W. side 30" Tw. W. Oak N17°W 47.15  
Set Std. Nail & tag NW side 12" Oak S53°W 96.35  
Set Std. Nail & tag NW side 12" Spruce N72 1/2°E 138.47  
Set Std. Nail & tage in SW side 12" Maple S29°E 77.65



Signed by Marvin E. Myers

Date Dec 18, 1993

Surveyor's Michigan License No. 31600

DATE Dec 7, 1993 PEER GROUP APPROVAL