

92463 1 8 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

Dec 28 10 28 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Robert J. Myers
REGISTERED SURVEYOR

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 23N R 3W	C - 5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-7-93

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on Nov 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO - May 1852 A.Curtis
Mon. - Post
WIT: 11" Y.Pine N32°E 13 lks.
13" Y.Pine S18°W 7 lks.
N46½°W 3.30 chains to Old Post
- 1955 G.Henning
Mon. - 1½" Pipe 12" deep
½" Bar set to surface
WIT: BT 10" B.Oak N59½°W 76.90'
BT 14" W.Oak N26°E 111.40'
P.Pole S50½°E 65.70'
- Aug. 1957 R.Ostling
Mon. - ½" Bar over 1½" Pipe
WIT: 10" B.Oak N53½°W 76.90'
P.Pole S50½°E 65.70'
14" W.Oak N26°E 111.40'
- L.2, pg. 368 Reg. of Deeds
Mon. - Mon. Box
WIT: C Lansing Rd.
- L.298, pg. 534 Sept. 1974 L.Cavanagh
Mon. - Spike in Pav't Box
- L.357, pg.228 Nov. 1978 K.Ostling
Mon. - Not given
WIT: 10" B.Oak N59½°W 76.90'
P.Pole S50½°E 65.70'
14" W.Oak N26°E 111.40'
- Oct. 1990 L.Cavanagh
Mon. - Cabin Spike in pav't box
WIT: Spike in P.P. N40°W 82.45'
Spike in P.P. N45°E 44.80'
Spike in P.P. S05°W 29.95'
15" Oak S50°E 44.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
Found 12" Cabin Spike over ½" inside of 1½" pipe inside pav't box in center line of roads N-S & E-W drove ½" bar into pipe verified position by measurement to accessories and corners of record and accepted as best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-Drove ½" bar down into pipe and set std. Roscommon County Monument over top in pav't box.
- Wit- Found Nail in SE side of P.P. N45°E 44.80
- Fd Nail in NE side of 20" Tw. Oak S50°E 45.4
- Fd Nail in E. side Power Pole S5°W 29.99
- Fd. Nail in SW side Power Pole N40°W 82.48
- Found power pole S50½°E 65.70



Signed by Marvin E. Myers

Date Dec 18, 1993

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

DATE Dec 7, 1993

PEER GROUP APPROVAL