

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE REMONUMENTATION SURVEY &
AND CORNER RECORDATION CERTIFICATE**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

22 NOV 94 11:09 A.M.

Roscommon (County) APR 24 1995 Located In: Corner Code #

ROBERT W. SMITH
REGISTER OF DEEDS
ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE 10-20-94 MRM

Register of Deeds Stamp & File Number

1. Public Land Survey	T	<u>23N</u>	R	<u>3W</u>	<u>G - 7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on October 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-Artemas Curtis 1852
Mon-Set Post
WIT: 10" Cedar N11°E 53 lks.
5" Spruce S61°W 9 lks.
- Henning 9-44
Mon-Set 3"x4" Cedar Post
WIT: Fd. old Spruce stump orig. cor.
Original US B.T. bears N11°E 43 lks.
Fd. 10" Cedar Mkd. NBT facing cor. S63 ½°E 9.90'
Mkd. NBT Cedar 5" N33 ½°W 8.60'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 3" x 2" Cedar Post monument rotted at ground level
The following accessories were found:
10" Cedar mkd. NBT S55°E 9.75' to blaze
13" Cedar with axe blaze N17°E 28.30' to blaze
8" Cedar with blaze N26°W 8.80' to blaze
9" Cedar with blaze N84°E 5.85' to blaze

Accepted as a perpetuation of the original Government corner.

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-Set Standard Roscommon County Monument stamped "T23N R3W G-7 31600"
WIT: Set Wit. Tag & Nail NE side 10" Cedar mkd. NBT S55°E 10.06'
Set Wit. Tag & Nail NW side 7" Cedar S23°W 3.34'
Set Wit. Tag & Nail W. side 5" Cedar N04°W 16.29'
Set Wit. Tag & Nail N. side 9' Cedar N66°W 26.95'
Set Carsonite Post West 3'±



Signed by Marvin E. Myers

Date NOV. 9, 1994

Surveyor's Michigan License No. 31600