

9245

FEB 18 1994

COMMISSION

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF ROSCOMMON

DEC 28 10 28 AM '93

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Robert E. Myers  
REGISTERED SURVEYOR

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 23N R 3W	H - 3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 12-7-93

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on Nov 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1852 A.Curtis	1952 Henning	L.312, pg. 327 Nov. 1975 R.Higgins
Mon. - Post	Mon. - Fd. 1 1/2" Pipe C. Rd. & fences	Mon. - Fd. Iron in pav't box
WIT: 12" W.Pine N49°W 22 lks.	WIT: NBT 8" W.Oak N56°W 66.40'	
20" W.Pine S30°E 9 lks.	NBT 10" W.Oak S46°E 53.00'	
	NBT 7" B.Oak N44°E 72.50'	

Misc. Records Reg. of Deeds  
Mon. - Iron in Mon. Box

May 1989 M.E. Myers	Oct. 1990 L.Cavanagh	
Mon. - Fd. 1/2" Bar in pav't box	Mon. - Bar in pav't box	
WIT: Nail SW face 12" W.Oak	WIT: Spike in 14" W.Oak N52°W 66.62'	
N50°W 66.60'	3" Oak N68°E 52.10'	
Stop Sign Post N25°W 34.40'	22" W.oak S48°E 52.45'	
No Outlet Sign Post N25°E 50.90'	12" W.Oak (clump) S33°W 75.50'	
North Cut Rd. Sign Post S40°E 30.70'		

L.631, pg. 283 M.E.Myers  
(same as Oct. 1990 L.Cavanagh)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2" bar over 12" Cabin Spike inside 1 1/2" pipe verified position by measurement to accessories and corners of record and accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon- Drove pipe down and set Std. Roscommon County monument over top.  
Wit- Found blazed 3" Oak N68°E 52.1  
Found blazed 22" Oak S48°E 52.45  
Found blazed 12" W. Oak S33°W 75.5  
Stop sign post N25W 34.4  
No Outlet Sign Post N25°E 50.9  
North Cut Road Sign Post S40°E 30.7  
Set Std. Nail & tag NE side 24" W. Oak S42°E 35.35  
Set Std. Nail & tag NW side 11" W. Oak S25°W 76.08  
Set Std. Nail & tag SW side 14" W. Oak N49°W 66.55  
Set Std. Nail & tag NW side 3" W. Oak N52°E 58.3



Signed by Marvin E. Myers Date Dec 18, 1993  
Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

DATE Dec 7, 1993 PEER GROUP APPROVAL