

Dec 28 10 28 AM '93

9242

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>3W</u>	<u>H - 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert H. ...
REGISTER

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 11-30-93

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5							●					
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on Nov 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1852 A. Curtis Mon. - Post WIT: 12" Maple N30°W 22 lks. 15" W.Pine S35°E 40 lks.	Oct. 1992 L. Cavanagh Mon. - 1/2"x18" Steel Bar WIT: 8" Balsam N25°W 10.67 9" W.Pine S04°E 30.50' 10" Maple S44°W 47.72' 7" Maple N37°E 11.80'
Nov. 1969 G. Henning Mon. - 1" Pipe in fence cor. WIT: 10" Balsam N35°E 17.50' 8" Balsam N41°W 13.00'	Nov. 1993 M.E.Myers L.631, pg. 283 Mon. - 1/2"x18" Steel Bar WIT: 8" Balsam N25°W 10.67' 9" W.Pine S04°E 30.50' 10" Maple S44°W 47.72' 7" Maple N37°E 11.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x18" bar & Cap #17614 verified position by measurement to accessories and corners of record and accepted as the best available evidence of the position for the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Std Roscommon County Monument
Wit- 8" Balsam Fir N25°W 10.67
9" W. Pine S04°E 30.50
10" Maple S44°W 47.72
7" Maple N37°E 11.80



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date Dec 21, 1993

DATE Nov 30, 1993 PEER GROUP APPROVAL