

**SURVEY &
REMONUMENTATION**

8573

APR 24 1995

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

Roscommon

(County)

Located In:

Corner Code #

5 DEC 94 9:22 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

- | | | |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T <u>23</u> N R <u>3</u> W | <u>H-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frank J. Arleth in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

William Burt Set post 1852
Spruce 5" N20°W 41ks
Spruce 6" S25°E 32 lks

Ostling 1960 fd. 6" squared post
scribed 1/4", No witness available.
See notes in dossier

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 1994 Arleth found remains of Post Set 1/2" x 42" bar in corner. Post was found by running line from the Northeast corner of Section 34 over 1/2" bar found for 1/8 corner. Total dist from Northeast corn to 1/4 corner is 2627.6'. Swamp crossing from the NE corner is 2408'- swamp is now flooded.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" x 42" Bar in Post remains H-11
N & T 8" maple N89°E 241.15' which is 1.0' North of Section line.
N & T 5" Birch S45°W 66.20'
N & T 6" Twin Birch S78°E 86.76'
1" pipe & cap #31600 N17°30'W 19.80'
Set carsonite survey marker at corner



Signed by Frank J. Arleth

Date 11/30/94

Surveyor's Michigan License No. #21266

Date 11/29/94 Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 182