

9243

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

DEC 28 10 28 AM '93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 23N R 3W	I - 3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Robert W. Myers
REGISTERED

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-7-93

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on Dec 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1852 A. Curtis	Oct. 1990 L. Cavanagh
Mon. - Post	Mon. - Set 1/2"x18" Bar
WIT: 6" W. Pine N45°E 28 lks.	WIT: 4" Oak N35°W 52.55
15" Y. Pine S39°W 21 lks.	15" Oak N52°E 29.10'
	10" Oak S40°E 57.10'
	6" Oak S65°W 49.48'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2"x18" bar and cap #17614 verified position by measurement to accessories of record and accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set in exact location Std. Roscommon County Monument.
 Wit- Std. nail & tag NE side 4" Oak N29°W 52.73
 Std. nail & E. side 15" Oak N26°E 29.62
 Std. nail & NW side 6" Oak S65°W 49.73
 Std. nail & tag NE 10" S34°E 57.38



Signed by Marvin E. Myers Date Dec 20, 1993
Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

DATE Dec 7, 1993 PEER GROUP APPROVAL