

9240

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

Dec 28 10 28 AM '93

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>3W</u>	<u>I - 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-7-93

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5									●				
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1852 A. Curtis	Oct. 1990 L. Cavanagh	1992 M.E. Myers
Mon. - Post	Mon. - Set 1/2"x24" Pipe	Mon- 1/2" pipe
WIT: 8" Tamarack N65°W 26 lks.	WIT: 4" Cedar N65°W 10.75'	Wit- Fd 4" Cedar N65°W 10.75
8" Tamarack S50°E 12 lks.	5" Cedar S40°W 8.70'	Fd 5" Cedar S40°W 8.70
	8" Cedar S47°E 11.00'	Fd. 8" Cedar S47°E 11.00
	7" Cedar N60°E 12.70'	Fd. 7" Cedar N60°E 12.70

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x24" Pipe verified position by measurement to accessories of record and accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon - Set Standard 2"x21" Roscommon County Monument
- Wit - Nail & tag N. side 4" Cedar N63°W 10.86
- Nail & tag NW side 8" Cedar N66°E 13.03
- Nail & tag N. side 8" Cedar S55°E 11.55
- Nail & tag E. side 5" Cedar S42°W 8.98
- Carsonite Post 2.38 West



Signed by Marvin E. Myers

Date Dec 27, 1993

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

DATE Dec 7, 1993 PEER GROUP APPROVAL