

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Roscommon Located In: _____ Corner Code # _____
(County)

1. Public Land Survey	T <u>23N</u> R <u>3W</u>	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED
26 SEP 96 3:38 P.M.
ROBERT W. SMITH
REGISTER OF DEEDS
TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on May, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Artemus Curtis set original
post April 1852
Cedar 15 N21W 31 links
Cedar 10 S54E 9 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A line was run from K-7 to G-7, a careful search was conducted in the area of double proportionate distance for this corner, post fragment was recovered with stump generally fitting NW witness, also fitting swamp crossing 0.5 chains West

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**
DATE Aug 16, 1996
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A perpetuation of the Original Government Corner.
Set Roscommon County Standard Monument (stamped 17614)
Wit: N&T in 12" Maple N80°W 58.43'
N&T in 5" Ash N30°W 22.43'
N&T in 4" Poplar N70°E 34.35'
Set Carsonite post South 1.05'



Signed by *Larry L. Cavanagh* Date 9-16-96
Surveyor's Michigan License No. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN, 1982