

9162

**ROSCOMMON COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MAY 28 1997

**COMMISSION**

For corners in

<u>ROSCOMMON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>23</u> NR <u>3W</u>	<u>L - 7</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

6 DEC 96 4:25 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

**TO BE FILED IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, TIMOTHY L. LAPHAM, in a field survey on July 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L - 7 GLO, CURTIS 1852, SET POST, 12" HEMLOCK N65W 37 LINKS, 10" BEECH 10" S55E 12 LINKS; LCRC, ROSER, 5/4/94 (REC 6/6/94 L1, P328), DNR MON, 12" MAPLE SOUTH 25.0', 7" MAPLE S42W 33.8', 20" TWIN OAK N10W 6.1', 12" OAK N80E 13.1';

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


L - 7 NO EVIDENCE OF GLO FOUND. FOUND DNR MONUMENT IN ACCORD WITH RECORDED LCRC. ACCEPTED FOUND MONUMENT AS BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. SEE DOSSIER FOR ADDITIONAL INFORMATION.

**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Aug 16, 1996**

*Marvin E. Myers MRR*  
**Marvin E. Myers, P.S.  
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L - 7 FOUND DNR MONUMENT FROM WHICH:  
SOUTH 25.0' 12" MAPLE N10W 6.1' 20" TWIN OAK  
S42W 33.8' 7" MAPLE N80E 13.1' 12" OAK  
Nail and tags in all trees



Signed by *Timothy L. Lapham*  
Surveyor's Michigan License No. 27595

Date 10/01/1996