

9165

SURVEY & REMONUMENTATION

ROSCOMMON COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

MAY 28 1997

COMMISSION

STATE OF MICHIGAN ROSCOMMON COUNTY RECORDED

6 DEC 96 4:25 P.M.

ROBERT W. SMITH REGISTER OF DEEDS

For corners in

Form with fields for ROSCOMMON (County), Located In, Corner Code #, and numbered sections 1-5 for survey details.

TO BE FILED IN LIBER 3 OF LAND CORNERS Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13 for recording corner positions.

I, TIMOTHY L. LAPHAM, in a field survey on July, 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M -6 BURT 1838, SET POST 6" Y.PINE S26W 20 LINKS, 6" Y.PINE N34W 26 LINKS; LCRC, JOHNSON, 1/28/92 (REC 1/28/92, L1, P305), FOUND 1/2" BAR, 8" RED OAK S38E 60.6', 6" RED OAK N61E 62.3', 5" RED OAK N62W 49.3', 12" RED PINE S86W 64.9'; LCRC, ROSER, NO DATE (REC 6/6/94, L1, P326), RE-RECORDED JOHNSON'S LCRC;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M -6 NO EVIDENCE OF GLO FOUND, FOUND 1/2" IRON IN ACCORD WITH RECORDED LCRC. ACCEPTED FOUND CORNER AS BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. SEE DOSSIER FOR ADDITIONAL INFORMATION.

ROSCOMMON COUNTY PEER GROUP APPROVAL DATE AUG 16 IN 1996

Signature of Marvin E. Myers, P.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M -6 SET 2"x24" CAST IRON MONUMENT WITH BRASS ROSCOMMON PLATE FROM WHICH: S38E 60.6' 8" RED OAK N62W 49.3' 5" RED PINE N61E 62.3' 6" RED OAK S86W 64.9' 12" RED PINE Nail and tags in all trees



Signed by [Signature] Surveyor's Michigan License No. 27595

Date 10/1/1996