

9539

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE APR 07 1998 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN ROSCOMMON COUNTY RECORDED

For corners in

Form with fields: Roscommon (County), Located In: Sec.31T 23NR 4W, Sec. 6 T 22NR 4W, Corner Code # C-13, C-1, and numbered items 1-5.

SECTION

29 DEC 97 3:48 P.M.

ROBERT W. SMITH REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on December 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. J. Brink, D.S. Nov 1839 Mon - Post in Swamp 18" deep Wit: No witnesses near

July 11, 1919 Beuthlen, Missaukee Co. Surveyor (prior to construction of M-55?) Profile notes Sta 36+31 County line Sta 64+64 1/4 Corner (2833') Sta 91+9 Sec. Cor (2645) Mon - None given Wit: None given

GLO A. Curtis, D.S. Sept 1852 Mon - Post Wit: 14" Y. Pine S11 1/4 W 11.25 lks 14" Y. Pine S00 12 E 11.35 lks

Nov 1968 G. D. Henning, R.L.S. Mon - Iron pavement box in corner Wit: Iron Pavement box in corner East 5280

MDOT plans Job# 15911A FRR # 72021 & FRR 68033 Sta 941+81.82 County line Sta 996+40.07 Sec. Cor. (5458.25 difference in sta) Mon - Boat Spike in Monument Box Wit: None given

L. 2, P. 426 Mon - Monument box in M-55

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

L. 253 P. 615 L.L. Cavanagh, R.L.S. May 19, 1971 Mon - Pavement Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 12" Cabin Pin over top of a Grader Blade in pavement monument box. Measured to corners of record N89°42'26"W 5459.36 and S89°44'53"E 5279.62. Accepted position as the best available evidence of the position of the Original corner. Drove Grader Blade down to 24" below surface set Standard Roscommon County monument in Pavement Monument Box over top of grader Blade.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Roscommon County Monument in pavement box. Wit: Nail & tag in East side 5' above ground Utility Pole S22°E 98.70' South Edge of Reflector Post N67°W 74.75' Carsonite Post in edge of Swamp S07°W 38.9' Carsonite post at water's edge of ditch N09°E 33.2'

ROSCOMMON COUNTY PEER GROUP APPROVAL

DATE DEC 22, 1997

Signature of Marvin E. Myers, P.S. County Surveyor



Signed by [Signature] Surveyor's Michigan License No. 31600

Date DEC 22, 1997