

9537

SURVEY & REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Sec. 31 T <u>23</u> NR <u>4</u> W	<u>D-13</u>
	Sec. 6 T <u>22</u> NR <u>4</u> W	<u>D-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		_____
5. Private Claims _____		_____

SECTION

STATE OF MICHIGAN  
 ROSCOMMON COUNTY  
 RECORDED  
 29 DEC 97 3:48 P.M.  
 ROBERT W. SMITH  
 REGISTER OF DEEDS  
 FILE IN LIBER 3 OF LAND CORNERS  
 Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on December 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. J. Brink, D.S. 1839  
 Mon - Post in Swamp to wet  
 To mound 16" deep  
 Wit: No witnesses near

July 11, 1919 Beuthien, Missaukee Co.  
 Surveyor (prior to construction of M-55?)  
 Profile notes Sta 36+31 County line  
 Sta 64+64 1/4 Corner (2833')  
 Sta 91+9 Sec Cor (2645')  
 Sta 117+60 1/4 Cor (2651')  
 Sta 130+35 1/8 cor (1325')  
 Mon - None given  
 Wit: None given

Nov 1968 G.D. Henning, R.L.S.  
 Mon - Computed Position  
 Wit: Iron pavement box East 2640  
 Iron pavement box West 2640

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	2						
5												
6	18	17	16	15	14	13						
7												
8	15	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monument or witnesses trees in the vicinity were found. Measured between existing monuments (5278.93)  
 Reestablishment of the position of the Government corner by proportional measure East 2639.47 ( 2640 GLO )  
 West 2639.46 ( 2640 GLO ) Set Standard Roscommon County monument in Pavement Monument Box.

Accepted as a careful and faithful establishment of the position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Roscommon County Monument in pavement box.  
 Wit: Nail & tag in East side (6'± above ground) Utility Pole S43°W 106.16'  
 North edge of reflector post N85°E 99.00'  
 Carsonite Post S05°W in Swamp 43.35'  
 Carsonite post at water's edge of ditch N06°E 38.1'



ROSCOMMON COUNTY  
 PEER GROUP APPROVAL  
 DATE DEC 22, 1997

*Marvin E. Myers*  
 Marvin E. Myers, P.S.  
 County Surveyor

Signed by *Marvin E. Myers*  
 Surveyor's Michigan License No. 31600

Date DEC 22, 1997

LIBER 3 PAGE 489