

ROSCOMMON COUNTY REMONUMENTATION

Dec 21 10 51 AM '93

REMONUMENTATION

FEB 18 1994
9077

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Robert Curtis
REGISTER

For corners in

ROSCOMMON (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23</u> N R <u>4</u> W	<u>E-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 11/30/93**

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, TIMOTHY L. LAPHAM, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12: 1852, A.CURTIS, POST, BEECH 12" N55E 15LKS, ELM 15" S60W 50LKS;
DATE UNKNOWN, SURVEYOR UNKNOWN, LCRC 2-427, CORNER MATERIAL, 2 WITNESSES;
9/22/1987, L.CAVANAGH, (132) 517-545, COR MAT, 4 WITS;
7/19/1989, L.CAVANAGH, LCRC 1-273, COR MAT, 4 WITS;
7/19/1989, L.CAVANAGH, SURVEY-SEE DOSSIER, NO COR MAT, 4 WITS;
6/26/1991, L.CAVANAGH, (132) 605-687, NO COR MAT, 4 WITS;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12: FOUND 1"X24" CAPPED PIPE/AXLE ROD
N50E 12.07' 3" MAPLE
S55E 14.53' 9" W. OAK
S04W 30.67' 5" ELM
N17E 6.48' 5" POPLAR
ACCEPTED FOUND CORNER AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER.
THIS CORNER ESTABLISHED IN ROSCOMMON COUNTY REMONUMENTATION PROGRAM.
SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12: SET 2" X 21" CAST IRON MONUMENT WITH BRASS ROSCOMMON COUNTY PLATE
AZ 125° 15.60' NAIL IN SOUTH FACE 7" W. OAK TWIN TO 10" W. OAK
AZ 47° 12.24' SPIKE & TAG IN SE FACE TWIN 3" MAPLE WITH BLAZE
AZ 20° 6.76' SPIKE & TAG IN EAST FACE 8" POPLAR WITH BLAZE
AZ 182° 30.85' SPIKE & TAG IN WEST FACE 8" ELM WITH BLAZE
AZ 105° 1.2' CARSONITE SURVEY MARKER POST
AZ 270° 17'+/- REMAINS OF OLD N-S FENCE



Signed by *[Signature]*

Date 12/20/93

Surveyor's Michigan License No. 27595

Date 11/30/93 Peer Group Approved