

8285

SURVEY & MONUMENTATION

ROSCOMMON COUNTY PEER GROUP APPROVAL

DATE APR 24 1995

LAND CORNER RECORDATION CERTIFICATE

STATE OF MICHIGAN ROSCOMMON COUNTY RECORDED

COMMISSION Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 23N R 4W	F - 9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

10 NOV 94 3:27 P.M.

ROBERT W. SKITH REGISTER OF DEEDS

ROSCOMMON COUNTY PEER GROUP APPROVAL DATE 9-15-94 Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

I, Marvin E. Myers, in a field survey on Sept 12 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Artemas Curtis 1852 Mon-Set Post WIT: 10" W.Pine N25°E 142 lks. 3" Tamarack S25°W 105 lks.

RCRC L.2, pg.416 LCRC Mon-DNR Alum. Cap WIT: 7" J.Pine S29°E 18.60' 7" J.Pine N19°E 43.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" pipe with DNR alum. and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-1 1/2" Iron Pipe with DNR alum. Cap WIT: Set Wit. Tag & Nail in S. side 3" Poplar S85°W 118.24' Set Wit. Tag & Nail in NE side 3" Poplar N45°W 125.93' Set Carsonite Post East 3.00' Set Nail W'ly shoulder Old US 27 S88°01'45"E 988.50' E-9 N89°00'13"W 2641.72' G-9 S88°59'47"E 2641.86'



Signed by Marvin E. Myers

Date OCT 11, 1994

Surveyor's Michigan License No. 31600