

JAN 24 1996

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-28-94

ROSCOMMON COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

| | | |
|---------------------------------------|--------------------------|------------------------|
| ROSCOMMON (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>23N</u> R <u>4W</u> | <u>L-7</u> |
| | T _____ R _____ | |
| | T _____ R _____ | <u>SURVEY 2</u> |
| | T _____ R _____ | <u>REMONUMENTATION</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | <u>APR 05 1996</u> |
| | S _____ T _____ R _____ | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

28 DEC 94 1:07 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

COMMISSION

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Timothy L. Lapham, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
L-7: 1852 CURTIS, SET POST, HEMLOCK 10" N55W 30LK., HEMLOCK 10" S70E 25LK.,
1943 HENNING SURVEY, NO CORNER MATERIAL OR WITNESSES
9/1943 HENNING SURVEY, NO CORNER MATERIAL OR WITNESSES
5/1986 CAVANAGH SURVEY NOT RECORDED, NO CORNER MATERIAL, 4 WITNESSES
6/1992 MYERS SURVEY 615-337, NO CORNER MATERIAL OR WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-7: FOUND 1/2"x18" IRON BAR AND REMAINS OF WOODEN STAKE, FOUND BLAZE ON UPROOTED TREE FOR 1 WITNESS, REMAINING WITNESSES GONE, DISTANCES EAST AND WEST MATCH HENNING SURVEY, ACCEPTED FOUND IRON AS BEST EVIDENCE OF ORIGINAL CORNER POSITION.
CORNER APPROVED AT PEER REVIEW MEETING 12-28, 1994. SEE DOSSIER FOR ADDITIONAL INFORMATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-7: SET 3/4"x60" BLACK PIPE WITH PLASTIC PS CAP #27595
N10E 23.37 SET NAIL AND TAG IN SE FACE OF 10" ASH
N64E 31.41 SET NAIL AND TAG IN NE FACE OF 14" ASH
N60W 33.84 SET NAIL AND TAG IN SW FACE OF 10" ASH
SOUTH 4.59 FACE OF CARSONITE POST



Signed by [Signature]
Surveyor's Michigan License No. 27595

Date 12/24/94