

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE 12-28-94

MEM

ROSCOMMON COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 24 1995

COMMISSION

For corners in
ROSCOMMON
(County)

Located In: Corner Code #

- 1. Public Land Survey T 23N R 4W M-5
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

**SURVEY &
REMONUMENTATION**
APR 05 1995

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

28 DEC 94 1:06 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

COMMISSION

Timothy L. Lapham in a field survey on December, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-5: 1838 BRINK, SET POST, HEMLOCK 10" N12W 17LK., MAPLE 10" S57-1/2W 24 LK.
DATE/SURVEYOR UNKNOWN, LCRC 2-377, 1/2" ROD 3 WITNESSES
9/1943 HENNING SURVEY, UNRECORDED, NO MATERIAL OR WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-5: FOUND 1/2x24" IRON ROD EXCAVATED TO 3' NO FURTHER EVIDENCE FOUND, DISTANCE SOUTH MATCHES HENNING SURVEY, ACCEPTED FOUND IRON AS BEST EVIDENCE OF ORIGINAL CORNER POSITION.
CORNER APPROVED AT PEER REVIEW MEETING 12-28, 1994. SEE DOSSIER FOR ADDITIONAL INFORMATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-5: SET 2-1/2"x24" CAST IRON MONUMENT WITH BRASS DISC MARKED 1994-27595
N55E 33.08 CENTERLINE N END 24" CULVERT
S41E 62.63 SET NAIL AND TAG IN NE FACE 15" ELM
S58W 50.24 SET NAIL AND TAG IN NW FACE 6" SPRUCE
N22W 24.49 SET NAIL AND TAG IN SE FACE 14" ELM
NORTH 33.69 FACE OF CARSONITE POST

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Signed by *[Signature]*

Date 12/27/94

Surveyor's Michigan License No. 27595

