

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
RUSCOMMON COUNTY
RECORDED

For corners in

Roscommon
(County)

Located In:

Corner Code #

1. Public Land Survey

T 23N R 1W

T 23N R 2W

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A-2
M-2

9 DEC 1999 2:33:08 PM

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on November 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - April 1839 J. Brink, DS
Mon - Post
Wit: 8" Cedar S23°W 40 lks
9" Birch N25½°W 27 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2"x4" Iron Pipe (typical M. Schaaf used in 1930's±) in remains of old 4" wood post; found stump hole N25°W 18.0 Replaced pipe with Standard County Monument. Accepted as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard County Corner
Wit: Set nail and tag in Northwest side 8" Spruce N45°E 22.95'
Set nail and tag in West side 12" Tw. Maple N37°W 14.00'
Set nail and tag in East side 8" Maple in (clump) S47°W 12.87'
Set nail and tag in Southeast side 8" White Pine S25°E 12.85'
Set Carsonite post West 2'

RUSCOMMON COUNTY

PEER GROUP APPROVAL

DATE NOV 30, 1999

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by [Signature]
Surveyor's Michigan License No. 31600

Date December 03, 1999

LIBER 3 PAGE 628

SMITH &
REGISTER OF DEEDS

NOV 11 2000

SECTION