

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

Roscommon
(County)

Located In:

Corner Code #

9 DEC 1999 2:33:18 PM

ROBERT W. SMITH
REGISTER OF DEEDS

- 1. Public Land Survey T 23N R 1W A-4
 T 23N R 2W M-4
 T R _____
 T R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on November 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 J. Brink, DS
Mon - 10' Birch

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 10' Tamarack growing out of Stump mound at computed position, dug into mound of decaying wood and soil set Standard County Monument in center mound at computed position. Accepted as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard County Corner
Wit: Set nail and tag in East side 10' Tamarack N4°W 2.91'
Set nail and tag in West side 8' Maple S35°W 19.08'
Set nail and tag in South side 10' Balsam S60°E 26.46'
Set nail and tag in North side 12' Balsam S85°W 17.18'
Set Carsonite post South 1'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 30, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Marvin E. Myers*
Surveyor's Michigan License No. 31600

Date December 03, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1986

LIBER 3 PAGE 629

MAY 14 2000

SECTION