

**SURVEY &
REMONUMENTATION**

APR 07 1998

SECTION

9241

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N	R 1W	A-11
T23N	R 2W	M-11
T	R	
T	R	

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

16 DEC 97 12:25 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNER:
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey November, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838
SET POST
MAPLE 18" N53W 40 LKS
CEDAR 8" S47W 39 LKS

GEORGE D. HENNING 2240 1974
LIBER 299, PAGE 493
FD 1/2" IRON

C.F. ROSER 12028 1966
FD 1/2" REINF. ROD
REINF. ROD IN CONC MON
N43W 49.4'

FRANK J. ARLETH 21266 1974
LIBER 297 PAGE 302
FD 1 1/4" PIPE IN BLACKTOP
WIT: CONC MON N45°W 48.0'

TOP. CTR. HWY. PROJ MK. (CONC)
N48E 42.70'
8" CEDAR S36E 60.81'
CTR N-S BIT. RD DUE WEST 3'
CTR BIT. RD. TO EAST DUE SOUTH 1'

LARRY L. CAVANAGH 17614 1978
ROD IN CONC MON N43°W 49.4'
TOP OF PROJECT MARKER (CONC)
N48°E 42.7'

FRANK J ARLETH #21266 1979
LIBER 364 PAGE 165
1/2" BAR
8" CEDAR S36°E 60.81'
TOP OF CONC MARKER N43°E 42.7'

FRANK J. ARLETH 21266 1979
LIBER 364 PAGE 694
SAME AS PREVIOUS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 24" BAR IN PAVEMENT BOX
PROJECT MARKER N48°E 42.7'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614, 1997
NAIL & TAG IN WEST GUARD POST (4" PIPE) TO N GAS RISER S48°E 44.76'
NAIL & TAG IN POWER POLE N51°E 46.33'
NAIL & TAG IN POWER POLE S45°W 44.73'
NAIL & TAG IN 9" CEDAR N54°W 60.30'
CARSONITE POST WEST 29.4'
PROJECT MARKER N48°E 42.7'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 5, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date Dec. 11, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 466