

**SURVEY &
REMONUMENTATION**

APR 07 1998

9237 SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N	R1W	<u>B-13</u>
T22N	R1W	<u>B-1</u>
T	R	
T	R	

16 DEC 97 12:23 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

I, Larry L. Cavanagh, in a field survey November, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838
SET POST
YELLOW PINE 14" N50W 8 LKS
WHITE PINE 22" N31E 33 LKS

C.F. ROSER 12028 1966
FD REMAINS OF SQ. CEDAR
POST AND 2 U.S.BT'S (STUMPS)
SET 4' X 1" PIPE (6" ABOVE GROUND)
AND BRANDED CEDAR GUARD
POST
16" OAK N50°E 52.79'
12" J. PINE DUE EAST 50.35'
14" OAK N70°W 37.93'
10" OAK S60°W 17.25'
(US-BT) 18" BLAZED YELLOW PINE
STUMP N50°W 5.0' (TO FACE)
(US-BT) 22" BLAZED WHITE PINE
STUMP N30°E 23.5' (TO FACE)
CTR OF E-W TRAIL DUE SOUTH 114'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE
12" J. PINE DUE EAST 50.35'
11" OAK S60°W 17.03'
(US-BT) BLAZED YELLOW PINE STUMP N50°W 5.0' (TO FACE)
(US-BT) BLAZED WHITE PINE STUMP N30°E 23.5' (TO FACE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


1" PIPE LEFT IN PLACE, DROVE CAP IN SIDE PIPE STAMPED 17614
NAIL & TAG IN 5" MAPLE N75°E 30.20'
NAIL & TAG IN 9" WHITE PINE N25°E 51.41'
NAIL & TAG IN 10" W. PINE S35°E 42.96'
NAIL & TAG IN 12" J. PINE DUE EAST 50.35'
NAIL & TAG IN 11" OAK S60°W 17.03'
CARSONITE POST NORTH 1.5'

A PERPETUATION OF THE ORIGINAL CORNER.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 5, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by Larry L. Cavanagh Date Dec 11, 1997
Surveyor's Michigan License NO. 17614



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
REVISED MAY 14, 1975
REVISED JAN., 1983