

**SURVEY &
REMONUMENTATION**

APR 07 1998

SECTION

9236

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

16 DEC 97 12:22 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

I. Public Land Survey

Located in:	Corner Code #
T23N R1W	C-13
T22N R1W	C-1
T R	
T R	

FILE IN LIBER 3 OF LAND CORNER

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey November, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	15		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838 SET POST WHITE PINE 28" N45W 13 LKS WHITE PINE 24" N63E 46 LKS	C F ROSER 12028 1966 FD 2 "MARKED" SQ. CEDAR POSTS TOGETHER AND 2 US-BT'S (STUMPS) SET 4.5' OF 1" PIPE (15" ABOVE GRD) AND BRANDED CEDAR POST 7" MAPLE S10W 59.10 7" R. PINE S62E 51.59 5" MAPLE N65E 37.82 11" W. BIRCH N40E 44.13 US-BT 24" BLAZED W. PINE STUMP N 65E 30.4' (TO FACE) US-BT 28" BLAZED W. PINE STUMP N45W 8' (TO FACE) CENTER OF E-W RR GRADE DUE SOUTH 83' EAST EDGE OF LOW WET AREA DUE EAST 10' CTR. OF N-S BEAVER TRAVELED STREAM BED DUE WEST 66'	1970'S L2 P149 1" X 4.5' PIPE & POST (15" ABOVE GRD) S10W 59.10' 7" MAPLE S62E 51.19' 7" R. PINE N65E 37.82' 5" MAPLE N40E 44.13' 11" W. BIRCH DUE SOUTH 83' CTR E-W RR GRADE N65E 30.4' US-BT 24" STUMP N45W 8' US-BT 28" STUMP
---	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" X 4.5' PIPE 15" ABOVE GROUND
15" MAPLE S10°W 59.20'
19" R. PINE S62°E 51.47'
12" MAPLE N65°E 37.94'
11" W. BIRCH N40°E 44.13 (NOW LEANING)
US-BT 24" BLAZED W PINE STUMP N65°E 30.4' (TO FACE)
US-BT 28" BLAZED W. PINE STUMP N45°W 8' (TO FACE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 1" X 4.5' PIPE. LEFT IN PLACE. DROVE CAP 17614 INSIDE PIPE.
NAIL & TAG IN 15" MAPLE S10°W 59.20'
NAIL & TAG IN 19" R. PINE S62°E 51.47'
NAIL & TAG IN 12" MAPLE N65°E 37.94'
NAIL & TAG IN 14" MAPLE N48°E 40.81'
CARSONITE POST N45°W 2.0'

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 5, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh Date Dec. 11, 1997
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 461