

OCT 05 1998

2021

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

Roscommon
(County)

Located In:

Corner Code #

20 APR 98 2:18 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

To be filed in Liber 3 of Land
Corners

Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>24N</u> R <u>1W</u> | <u>D-13</u> |
| | T <u>23N</u> R <u>1W</u> | <u>D-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on March 2, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1838 Lewis Clason, DS
Mon. - Post
10° Tamarack N39°E 20 links
9° Tamarack N58 1/2°W 34 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2"x36" pipe 1' above grade with old 4" x 4" post 0.5' South. I believe this is a Schaaf monument set in the swamp without a concrete base. Accepted as the best available evidence of the position of the Original Corner. Replaced Pipe with Standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Roscommon County Monument.
Wit: Set carsonite Post 1' South.
Set nail & tag in East face 3" Tamarack S37°W 48.52'
Set nail & tag in North face 4" Tamarack N56°W 42.10'
Set nail & tag in East face Power Pole N28°W 193.56'
Set nail & tag in West face Power Pole N63°E 278.51'

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE MARCH 27th 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600



Date April 10, 1998

LIBER 3 PAGE 1194