

**SURVEY &
REMONUMENTATION**

APR 07 1998

SECTION

9235

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

16 DEC 97 12:22 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in
Roscommon County

1. Public Land Survey

Located in:	Corner Code #
T23N R1W	D-13
T22N R1W	D-1
T R	
T R	

FILE IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey November, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		4		3		2		1			
3													
4		7		8		9		10		11		12	
5													
6		15		17		15		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838
SET POST BALSAM 8" N66 1/2E 13 LKS
BALSAM 8" N66 1/2E 13 LKS
BALSAM 7" N14W 13 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE FOUND
FENCE CORNER WEST 60°, NORTH 52°, FENCE RUNNING SOUTH & EAST, NOT USED AS EVIDENCE FOR CORNER LOCATION.
SET AT SINGLE PROPORTIONATE DISTANCE BETWEEN C-13 (N88°47'46"W 2638.90') AND E-13 (S88°47'46"E 2638.90')


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614 1997
NAIL & TAG IN 12" MAPLE SOUTH 18.40'
NAIL & TAG IN 7" MAPLE EAST 21.68'
NAIL & TAG IN 10" MAPLE S75°W 56.46'
NAIL & TAG IN 10" MAPLE N35°W 68.55'
CARSONITE POST NORTH 1.5'

A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

**ROSCOMMON COUNTY
PEER GROUP APPROVAL**
DATE Dec 5, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh Date Dec. 11, 1997
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 460