

**SURVEY &
REMONUMENTATION**

8374

APR 24 1995 ROSCOMMON COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23</u> R <u>1</u> W	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

15 NOV 94 9:13 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

I, Frank J. Arleth, in a field survey on November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
William Burt set post 1852
Aspen 8" S16°E 31 Lks
W. pine 24" N73°W 50 Lks

Ostline March 1964 Set 1/2" x 24" bar
Wit: 8' J. Pine N44°E 26.7
5" J. Pine S14°W 33.8
1" bar 330 feet West on Lake shore

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
November 1994 Arleth found 1/2" bar set by Ostling in 1964.
Wit: 8" J. Pine N44°E 26.7 (now dead)
5" J. pine S14°W 33.8 (blown down)
Iron fence post East 0.5' (still standing)
1/2" bar West 330.0 feet to lake shore



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Roscommon County standard monument H-7
N & T 6" Tamarack N77°W 34.47
N & T 6" Aspen S44°W 21.15
N & T 6" Birch N5°E 23.05
N & T 18" Birch N64°W 34.70
Old Blaze dead 8" J. pine N44°E 26.7
Iron fence post East 0.5'
1/2" bar west 330.0'
Set Carsonite Post next to corner.

Signed by Frank J. Arleth Date 11/11/94
21266 P.S.

Surveyor's Michigan License No. _____ DATE 11/10/94 Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 154